Risk Assessment Assemble and rig camera crane



The people that might be harmed: Studioworks employees, contractors, public, artists

| HAZARD | CONTROL |
|---|--|
| Awkward Body position whilst undertaking this activity. | Follow safe manual handling procedures. |
| Awkward, heavy load. | • Use 2-person lift, or break down into component parts.2 |
| Trapped hands and fingers. | • Use of competent operators to carry out the task. |
| Incorrect assembly procedure. | Visual check of cables and equipment prior to handling. |
| Arm out of balance and unsupported. | Follow any instructions provided for equipment in use. |
| Overloaded crane arm or panning head. | Ensure that the arm is correctly supported whilst the crane is being assembled and rigged with the camera and accessories. |
| • Risk of Dolly and arm falling over due to unlevel / uneven ground | Ensure that the arm is correctly supported when adjusting the load. |
| | • Ensure that the loads applied to the crane base, arm or panning head do not exceed the safe working limits. |
| | • Ensure Base is level. Take extra care when moving (unload arm) |