

Risk Assessment Camera assistance on location

The people that might be harmed: Studioworks employees, contractors, public, artists

HAZARD	CONTROL
 Awkward body positions and movements whilst undertaking task. Repetitive movements. Moving heavy loads, possibly over a considerable distance. Danger of electric shock from damaged cables or equipment. Danger of cables being caught and pulling equipment or objects over causing injury. Extreme weather conditions causing risk of additional tiredness, muscle strain, hypothermia, dehydration and sunburn. Uneven, wet, or icy surfaces creating risk of slipping and falling. Risk of falling or dropping equipment when working at height. Increased risk of personal injury after prolonged period of working. Risk of injury to those who have a pre-existing medical condition or are pregnant. Working in a public space with potential for injury due to actions of members of the public. 	 Follow safe manual handling procedures. Split large items into more manageable components. Use trolleys. Check all cables and equipment for mechanical damage. Ensure that Mains powered equipment and cables have been PAT (Portable Appliance Test) tested and comply with the EAW (Electricity at Work) regulations. Mains cables should be connected via a RCD (residual current device). Care should be taken with the routing of cables and covered with a mat in areas of pedestrian traffic. Cables should have sufficient slack and not be taut. Suitable clothing to be worn for the weather. Suitable footwear to be worn for the conditions. Follow working at height regulations. Bond any equipment that could fall. Be aware of risks due to tiredness. Ensure adequate rest breaks are provided and taken. Do not undertake a risk if you believe you will risk injury by doing so. The public should be kept away from any equipment or the movement of equipment. If there are large numbers of the

public or hostile crowds are possible security may be needed.

File: Camera assistance on location

Version: Version 1.1 Last Reviewed: 05/07/23